Comparative Statement

Nme of Work Construction of Compound Wall,Inter lock tiles Gate to Indira Canteen in Ward No.14

Sl. No	Description of work	Unit	Qty	Sanctioned Rate		Sriramareddy		Kumar BJ		Manjunth S	
				Rate	Amount	Quated Rate	Amount	Quated Rate	Amount	Quated Rate	Amount
	2	3	4	5	6	7	8	9	10	11	12
1	Earthwork excavation by manual means in Ordinary soil invovling an average horizontal throw upto 2meters and an average lift upto 1.5m. Excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. (Page no-142, Item no-19.2) including disposing of excavated earth at a lead of 9kms	Cum	52.15	183.72	9581.00	180.00	**9387.00**	185.00	**9647.75**	190.00	**9908.50**
2	Providing and constructing granite / trap / basalt size stone masonry in Foundation with cement mortar 1 :6, and hammered dressed in courses not less than 20cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	cum	61.76	4438.22	274104.00	4400.00	**271744.00**	4450.00	**274832.00**	4460.00	**275449.60**
3	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	91.50	103.88	9505.00	100.00	**9150.00**	105.00	**9607.50**	110.00	**10065.00**
4	Providing and constructing precast concrete solid blocks with compressive strength not less than 4.00 Newton per sqm with cement mortar 1:4 masnory (quoin, Jamb, closer blocks) with solid blocks of size 400X150X200cms confirming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffoldin, curing complete as per specifications	Sqm	109.80	961.42	105564.00	960.00	**105408.00**	960.00	**105408.00**	980.00	**107604.00**
5	Providing 20mm thick cement plaster in single coat with cement mortar 1:6, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per	Sqm	219.60	274.54	60289.00	270.00	**59292.00**	270.00	**59292.00**	280.00	**61488.00**

Scanned by CamScanner

6	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size gaded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459 Cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted for coping, including cost of all materials, Jabour, HOM of machinery, curing complete as per specification	Cum	3.65	5610.58	20479.00	5600.00	20440.00	5680.00	20732.00	5700.00	20805.00
	Total Amount				479522.00		475421.00		479519.25		485320.10
	% Percentage						-0.86		0.00		1.21

As per Comparative Statement rate quoted by Class -1 Contractor Sri.Sriramareddy is Rs.475421.00 Which is 0.86 % Below for Sanctioned Tender amount Hence the Sri.Sriramareddy quated amount Rs.475421.00 is recommanded for kind approval .

Executive Engineer
Dasarahalli Division
BBMP

Recommended for approval

ಮುಖ್ಯ [illegible]
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Scanned by CamScanner